经济技术指标

序号	名 称		单位	数量	备 注
1	总用地面积		㎡	1900.00	约合2.85亩
其中	建筑基底面积		㎡	634.10	
	绿地面积		㎡	573.64	
	硬化面积		㎡	692.26	
2	规划总建筑面积		㎡	2708.84	
3	地上建筑面积		㎡	2671.72	
其中	培训楼建筑面积		㎡	2635.81	
	附属用房建筑面积		㎡	73.03	
	其中	地上建筑面积	㎡	35.91	
		地下建筑面积	㎡	37.12	
4	容积率			1.41	
5	建筑密度		%	33.4	
6	绿地率		%	30.2	
7	停车位		辆	8	

北

南大里农业科技发展中心建设用地

X=3898774.411
Y=525485.417

X=3898761.771
Y=525522.773

X=3898750.415
Y=525514.883

X=3898735.641
Y=525453.844

X=3898711.666
Y=525483.310

X 3898707.690
Y 525481.108

培训楼

建设用地范围线

混凝土路面

透水砖路面

铺砖

水泥

出入口

箱变

电动推拉门

消防取水口

300m³消防水池

附属用房

1F\1D

地面标高

840县道

总平面规划图 1:200

备注 NOTE

1. 本图经初步设计审查机构及消防审批部门审查合格方可用于施工，
2. 版权属中盛弘宇建设科技有限公司所有，未经书面许可，不得擅自使用、更改和复制等其他用途。
3. This drawing can only be used for construction after being examined to be qualified and approved by Drawing Appraisal Unit & Fire Control Committee. The copyright belongs to zhongsheng hongyu construction technology co., LTD. Without written permission, it's prohibited to use, change or copy the drawing for other purposes.

合作设计单位 CO-OPERATED WITH

说明 EXPLAIN

审 定 APPROVED BY	王铭铭	
审 核 VERIFIED BY	徐 敬	
项目负责人 PROJECT CHIEF	赵 璇	
专业负责人 DIVISION CHIEF	王铭铭	
校 对 CHECKED BY	关国涛	
设 计 DESIGNED BY	杨惠民	

建设单位 CONSTRUCTION
夏县南大里乡人民政府

工程名称 PROJECT
南大里乡“夏鲜”蔬菜产业园区及产城融合示范区建设项目

项目名称 SUB PROJECT
南大里农业科技发展中心总图

图纸名称 DRAWING TITLE
总平面规划图

工程编号 JOB NO.	22YC-43		
阶段 STAGE	方案	专业 DISCIPLINE	建筑
比例 SCALE	1:100	图号 DWG NO.	全
日期 DATE	2023.02	版本号 VERSION NUMBER	A

中盛弘宇建设科技有限公司
Zhongsheng Hongyu Construction Technology Co.,Ltd.

工程设计资质证书编号
建筑甲级:A113007169
园林甲级:A113007169
规划乙级:城规142010
市政乙级:A213007166
人防乙级:A213007166

签字齐全 盖章有效